



## Scope of Work

PROJECT NAME:	King City
PROJECT LOCATION:	17165 SW Pacific Highway, King City, Oregon, 97224
PROJECT DESCRIPTION:	16 Attached Townhomes, 3 Buildings Total
SCOPE OF WORK:	Countertop and Backsplash
DATE OF WORK:	Fall 2024
BID DUE DATE:	August 11 <sup>th</sup> , 11:59pm, 2024
Duration:	Measure - 1 day per building Fabricate - 10 days per building Install - 1 day per unit (5 days for 5-plex, 6 days for 6-plex) Habitat superintendent to communicate exact dates

### Scope of Work:

1. Provide and install 1/2" acrylic countertop and 4" backsplash in all kitchens and bathrooms. Include 1-1/2" drop edge face.
2. Provide and install solid surface at bathroom windowsill, per plan.
3. Provide and install level 5/8" plywood sub-deck.
4. Field measure for countertops after cabinets have been installed.
5. Fabricate acrylic countertops off site.
6. Cut countertop and notch edge as necessary to accommodate sinks.
7. Provide color options in bid.